## SHIMOGA DISTRICT BOARD.

*Notification dated 31st January 1933.*

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Shimoga, up to 25th February 1933, for sinking a Draw Well for the use of the travellers, etc., at Gourikere Mutt in the Sorab Taluk, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plan and detailed estimate may be seen at the District Board Office, Shimoga, on working days between the hours of 11 A.M. and 5 P.M.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money and be superscribed "Tenders for sinking a well at Gourikere Mutt, Sorab Taluk, Shimoga District," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, and in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

10. Tenders which quote rates as "Estimated rates" on some per cent more or less will not be considered.

11. No claims for enhanced rates will be entertained on any account after acceptance of tender.

12. The accepted tenderer is bound to execute the work as per his bond and to receive payment to the extent of grant sanctioned.

13. Any unforeseen items found necessary during execution will be paid at current scheduled rates.

*Abstract.*

| No. | Items of work | Unit | Rate | Quantity | Remarks |
|---|---|---|---|---|---|
| | | | Rs. | | |
| 1 | Clearing the site all round .. .. | L. S. | | ... | |
| 2 | Excavating all soils ... ... . | C.yds. | | 176 | |
| 3 | Cut laterite brick with a lead of 3 miles revetment. | C.ft. | | 1767·8 | |
| 4 | Jelly backing ... ... ... | C.yds. | | 58·1 | |
| 5 | Providing Nelly-wood frame for the bottom ... | L.S. | | | |
| 6 | Scaffolding when under excavation to protect the sides. | ,, | | ... | |
| 7 | Bailing out water ... ... ... | ,, | | ... | |
| 8 | Constructing a temporary shed over the well ... | ,, | | ... | |
| 9 | Cut laterite in chunam mortar.— | | | | |
| | Parapet long walls .. .. | C.ft. | | 81 | |
| | Parapet cross walls ... ... | ,, | | 54 | |
| | Piliars over parapet walls .. ... | ,, | | 18 | |
| | Platform around parapet Longitudinal ... | ,, | | 145½ | |
| | Cross .. ... .. | ,, | | 67½ | |
| 10 | Burnt stone cross beam dressed and put up ... | S.ft. | | 15 | |
| 11 | Providing burnt stone slabs.— | | | | |
| | Parapet walls.— | | | | |
| | below longitudinal walls ... .. | S.ft. | | 36 | |
| | below cross walls .. ... | ,, | | 24 | |
| | Above longitudinal walls ... ... | ,, | | 27 | |
| | Above cross walls .. ... | ,, | | 9 | |
| 12 | Chunam pointing to parapet walls and platform. | Sqrs. | | 3·00 | |
| 13 | Providing wooden pulley with iron fillings .. | 1 | | 1 | |

H. SIDDAIYA,